

Fremantle Surf Life Saving Club					
Finishes Schedule - Version 1 (23/07/08)					
<i>Room</i>	<i>Area</i>	<i>Ceiling</i>	<i>Wall</i>	<i>Floor</i>	<i>Additional Items</i>
Ground Level Internal Areas					
Equipment Store & Workshop	375	plasterboard	plasterboard	concrete	
Rescue & First Aid	31	plasterboard	plasterboard	vinyl	
Members Gym	114	plasterboard	plasterboard	carpet & underlay	a/c
Clothing Shop	15	plasterboard	plasterboard	carpet	a/c
Admin	30	plasterboard	plasterboard	carpet	a/c
Female Change	44	plasterboard	tiles	vitrified tile	lockers
Male Change	44	plasterboard	tiles	vitrified tile	lockers
Corridor	106	glazing	plasterboard	vitrified tile	
Disabled WC	5	plasterboard	tiles	vitrified tile	
Members Bar	126	plasterboard	plasterboard	carpet	bar
Kitchen/Bar/Canteen	31	plasterboard	tiles to full height	rubber tiles	domestic style kitchen
Training Room 1	63	plasterboard	plasterboard	carpet	split a/c
Training Room 2	63	plasterboard	plasterboard	carpet	split a/c
Training Room 3	63	plasterboard	plasterboard	vinyl	split a/c
Training Room 4	62	plasterboard	plasterboard	vinyl	split a/c
Store room	30	plasterboard	plasterboard	tiles	split a/c
<i>Subtotal</i>	<i>1202</i>				
First Floor Internal Areas					
Restaurant	290	plasterboard/bare	glazing/plasterboard	bare concrete	service connections, louvres
Observation Post	23	plasterboard	plasterboard	vinyl	tinted glass
Light Well	65	glazing	plasterboard	n/a	
Roof Access	5				
<i>Subtotal</i>	<i>383</i>				
First Floor External Areas					
Restaurant Terrace	182	n/a	n/a	tiles	glass balustrade
Restaurant Entry	50	plasterboard/bare	plasterboard	bare concrete	
<i>Subtotal</i>	<i>232</i>				
TOTAL	1585				